



Completion of testing series double-spoke cavity cryomodules for ESS



UPPSALA
UNIVERSITET

R. Santiago Kern, C. Svanberg, K. Fransson, K. Gajewski, L. Hermansson, H. Li, T. Lofnes,
A. Miyazaki†, M. Ovegård, I. Profatlova, R. Ruber‡, M. Zhovner, Uppsala University, Uppsala, Sweden
R. Ruber, Thomas Jefferson National Accelerator Facility, Newport News, Virginia, United States

The FREIA Laboratory in Uppsala, Sweden, is a leading laboratory in accelerator R&D and currently responsible of testing the 13 double-spoke cryomodules (plus one spare) for the European Spallation Source (ESS) in Lund. These cryomodules have two double-spoke cavities each, are assembled at Laboratoire Irène Joliot-Curie (IJCLab), in Paris (France), and transported to FREIA for testing. In this regards FREIA counts with its own helium liquefaction plant and suitable radio-frequency power stations.

Challenges in Cryomodule Testing




Figure 1. Infrastructure components for cryomodules testing in FREIA.

From the 13 cryomodules tested, 5 of them had to be sent to IJCLab for repairs, bringing the total number of tests done at FREIA up to 18. All these cryomodules were tested once again at FREIA after being repaired and all were accepted.

Standard Testing Schedule for Cryomodule

week	MON	TUE	WED	THU	FRI	SAT	SUN
1st week	departure from Orsay	transport	reception	reception test			
2nd week	doorknob mounting	installed in bunker	cryogenic connection	vacuum connection	RF calibration at warm	pumping	
3rd week	coupler warm conditioning				LN shield cooling		
4th week	cooling down to 4K	4K filling	thermal action	2K pumping	multistep conditioning	CTS test	
5th week	heat load measurement	start warming up	warming up	warming up	warming up	warming up	
6th week	out from bunker	dismount doorknob, dry N2	out going test	departure	arrival at ESS		

Legend: Mechanical work (yellow), RF coupler conditioning (green), Cold test (blue)

Main part of the test takes 4 weeks.

Table 1. An overview of the disqualified cryomodules and the reason for the disqualification.

CM #	Issue
CM02	Stepper motor lack of response
CM03	Stepper motor lack of response
CM04	Stepper motor lack of response Vacuum leak in FPC's double wall tube
CM09	Vacuum leak in FPC's double wall tube
CM10	Stepper motor lack of response

Warm RF coupler conditioning




Figure 2: Comparison of the FPC conditioning. The fundamental power couplers, pre-conditioned at IJCLab in pairs via travelling wave up to 400 kW and standing wave up to 170 kW, are also conditioned at FREIA with a standing wave up to 400 kW at both room temperature and 2 K.

- Some couplers were repaired & recycled from disqualified cavity strings due to a vacuum leak.
- There is a big variation in conditioning time: from 10 h to 100 h, even under the same conditions.
- More active pumping during assembly might reduce the necessary conditioning time.
- RGA sometimes observed CH and oxygen have a negative correlation.




Figure 3. Data from RGA during warm RF coupler conditioning.

Cryomodules' Heat Loads and Q₀




Figure 4: Power dissipated in the cryomodules at different accelerating gradients. An average of the static heat load and the measurement resolution are added for comparison purposes (left). Cavities' quality factor Q₀ values from the vertical tests at IJCLab (right)




Figure 5: Field emission onset cavity (DSPK#) comparison between vertical VT (IJCLab) and cryomodule CM (FREIA) tests. HPR after VT, not tested afterwards

Cold Tuning System




Figure 6: Measured tuning range of the piezo actuators in Hz with respect to hosting cavity's LFD at 9 MV/m.

Very important for future cryomodule development to stress test one prototype and one series motor actuator




Figure 7: Motor tuning distance to nominal frequency and sensitivity.

Lesson learned

From 2 ½ years of testing:

- Helium recovery capacity: increased mid testing (not a bottleneck)
- Heat load measurement: add new flowmeter with a lower range in parallel
- FPC cooling: add ScHe circuit
- RF stations
 - Failures with tetrodes, power supplies and amplifiers → problems with schedule
 - Careful optimization of operation parameters, risk analysis and availability of spare parts
- In day-to-day activities
 - Good planning and overview, and → **Necessary**
 - Good understanding of what processes or activities can be done or prepared in parallel

Essential