




UPPSALA
UNIVERSITET



COMPLETION OF TESTING SERIES DOUBLE-SPOKE CAVITY CRYOMODULES FOR ESS

Rocío Santiago Kern

on behalf of the FREIA team



- The FREIA Team
- The ESS double-spoke cryomodules
- Cryomodules' Journey
- Challenges in Cryomodule Testing
- Measurements
 - Standard Testing Schedule per Cryomodule
 - Series Cryomodule Testing Qualification Overview
 - Warm RF coupler conditioning
 - Cryomodules' cooling
 - Cryomodules' Heat loads and Q_0
 - Field Emission
 - Risk of quench and protection
 - Cold tuning system and Lorentz-force Detuning
- Lessons learned
- Future prospects



The FREIA Team



International experts from different fields



Lars - T




Jefferson Lab






The European Spallation Source



Courtesy C. Maiano




Operation parameters


- 90 MeV \rightarrow 216 MeV
- Peak current 62.5 mA
- Bunch length 2.86 ns
- RF pulse length 3.2 ns
- Repetition rate 14 Hz
- RF duty cycle 4.5 %
- Temperature 2 K
- Max RF power 335 kW

parameter	value
f [MHz]	352.210
β_{opt}	0.50
E_{acc} [MV/m]	9.0
B_{pk}/E_{acc} (B_{pk})	6.8 (61 mT)
E_{pk}/E_{acc} (E_{pk})	4.3 (38 MV/m)
G [Ω]	133
R/Q [Ω]	427
L_{acc} [m]	0.639
Q_{ext}	1.75-2.85e5
BW [kHz]	1.2-2.0
Q_0	$>1.5e9$

CM= x2 double-spoke cav



(x13+1)




Operation parameters

- 90 MeV → 216 MeV
- Peak current 62.5 mA
- Bunch length 2.86 ns
- RF pulse length 3.2 ms
- Repetition rate 14 Hz
- RF duty cycle 4.5 %
- Temperature 2 K
- Max RF power 335 kW

parameter	value
f [MHz]	352.210
β_{opt}	0.50
E_{acc} [MV/m]	9.0
B_{pk}/E_{acc} (B_{pk})	6.8 (61 mT)
E_{pk}/E_{acc} (E_{pk})	4.3 (38 MV/m)
G [Ω]	133
R/Q [Ω]	427
L_{acc} [m]	0.639
Q_{ext}	1.75-2.85e5
BW [kHz]	1.2-2.0
Q_0	>1.5e9

CM= x2 double-spoke cav



(x13+1)

Cryomodules' Journey

Cryomodule Assembly at Orsay



2 000 km



Assesment at Uppsala





700 km

Installation at Lund






Challenges in Cryomodule Testing







Challenges in Cryomodule Testing




Challenges in Cryomodule Testing




Challenges in Cryomodule Testing




Challenges in Cryomodule Testing



Challenges in Cryomodule Testing



Challenges in Cryomodule Testing



FREIA is leading **low-β cryomodule** assessment in Europe



Standard Testing Schedule per Cryomodule



week	1st week													
day	MON		TUE		WED		THU		FRI		SAT	SUN		
	m	a	m	a	m	a	m	a	m	a				
activity	departure from Orsay		transport				reception		reception test					
week	2nd week													
day	MON		TUE		WED		THU		FRI		SAT	SUN		
	m	a	m	a	m	a	m	a	m	a				
activity	doorknob mounting	installed in bunker		cryogenic connection		vacuum connection		RF calibration at warm		pumping				
week	3rd week													
day	MON		TUE		WED		THU		FRI		SAT	SUN		
	m	a	m	a	m	a	m	a	m	a				
activity	coupler warm conditioning						LN shield cooling							
week	4th week													
day	MON		TUE		WED		THU		FRI		SAT	SUN		
	m	a	m	a	m	a	m	a	m	a				
activity	cooling down to 4K	4 K filling	thermalization	2K pumping			multipacting conditioning		CTS test					
	f vs T measurement	coupler cold conditioning		f vs p	calibration at cold									
week	5th week													
day	MON		TUE		WED		THU		FRI		SAT	SUN		
	m	a	m	a	m	a	m	a	m	a				
activity	heat load measurement	start warming up		warming up				warming up completed						
week	6th week													
day	MON		TUE		WED		THU		FRI		SAT	SUN		
	m	a	m	a	m	a	m	a	m	a				
activity	out from bunker		dismount doorknob, dry N2		out going test		departure		arrival at ESS					

Legend	
	Mechanical work
	RF coupler conditioning
	Cold test



Standard Testing Schedule per Cryomodule



week	1st week														
day	MON		TUE		WED		THU		FRI		SAT	SUN			
	m	a	m	a	m	a	m	a	m	a					
activity	departure from Orsay		transport				reception		reception test						
week	2nd week														
day	MON		TUE		WED		THU		FRI		SAT	SUN			
	m	a	m	a	m	a	m	a	m	a					
activity	doorknob mounting		installed in bunker		cryogenic connection		vacuum connection		RF calibration at warm			pumping			
week	3rd week														
day	MON		TUE		WED		THU		FRI		SAT	SUN			
	m	a	m	a	m	a	m	a	m	a					
activity	coupler warm conditioning								LN shield cooling						
week	4th week														
day	MON		TUE		WED		THU		FRI		SAT	SUN			
	m	a	m	a	m	a	m	a	m	a					
activity	cooling down to 4K		4 K filling		thermalization		2K pumping		multipacting conditioning		CTS test				
	f vs T measurement		coupler cold conditioning		f vs p		calibration at cold								
week	5th week														
day	MON		TUE		WED		THU		FRI		SAT	SUN			
	m	a	m	a	m	a	m	a	m	a					
activity	heat load measurement		start warming up		warming up				warming up completed						
week	6th week														
day	MON		TUE		WED		THU		FRI		SAT	SUN			
	m	a	m	a	m	a	m	a	m	a					
activity	out from bunker		dismount doorknob, dry N2		out going test		departure		arrival at ESS						

Legend	
	Mechanical work
	RF coupler conditioning
	Cold test

Main part of the test takes 4 weeks


Inevitable 18 days

- Beam Vacuum Pumping: 3 days
- Coupler conditioning 24h x 3-4 days
- Thermalization 7 days for CTS
- Warming up 4 days

Mechanical work takes more than 1 week but **overlapping** with other modules helps




Series Cryomodule Testing Qualification Overview






Series Cryomodule Testing Qualification Overview






Series Cryomodule Testing Qualification Overview



13 CMs tested



Series Cryomodule Testing Qualification Overview




13 CMs tested

8 CMs qualified in 1st round



Series Cryomodule Testing Qualification Overview





13 CMs tested

8 CMs qualified in 1st round

5 CMs disqualified on 1st round




Series Cryomodule Testing Qualification Overview



CM #	Issue
CM02	Stepper motor lack of response
CM03	Stepper motor lack of response
CM04	Stepper motor lack of response Vacuum leak in FPC's double wall tube
CM09	Vacuum leak in FPC's double wall tube
CM10	Stepper motor lack of response




Series Cryomodule Testing Qualification Overview




13 CMs tested
 ↪ 8 CMs qualified in 1st round
 ↪ 5 CMs disqualified on 1st round

CM #	Issue
CM02	Stepper motor lack of response
CM03	Stepper motor lack of response
CM04	Stepper motor lack of response Vacuum leak in FPC's double wall tube
CM09	Vacuum leak in FPC's double wall tube
CM10	Stepper motor lack of response






Series Cryomodule Testing Qualification Overview




13 CMs tested
 ↻ 8 CMs qualified in 1st round
 ↘ 5 CMs disqualified on 1st round





CM #	Issue
CM02	Stepper motor lack of response
CM03	Stepper motor lack of response
CM04	Stepper motor lack of response Vacuum leak in FPC's double wall tube
CM09	Vacuum leak in FPC's double wall tube
CM10	Stepper motor lack of response

↳ Under investigation by IJClab and the vendor

Series Cryomodule Testing Qualification Overview




13 CMs tested
 ↪ 8 CMs qualified in 1st round
 ↪ 5 CMs disqualified on 1st round




CM #	Issue
CM02	Stepper motor lack of response
CM03	Stepper motor lack of response
CM04	Stepper motor lack of response Vacuum leak in FPC's double wall tube
CM09	Vacuum leak in FPC's double wall tube
CM10	Stepper motor lack of response

↪ Under investigation by IJCLab and the vendor

Series Cryomodule Testing Qualification Overview



13 CMs tested
 ↪ 8 CMs qualified in 1st round
 ↪ 5 CMs disqualified on 1st round




CM #	Issue
CM02	Stepper motor lack of response
CM03	Stepper motor lack of response
CM04	Stepper motor lack of response Vacuum leak in FPC's double wall tube
CM09	Vacuum leak in FPC's double wall tube
CM10	Stepper motor lack of response

Found only after cooldown!

↳ Under investigation by IJCLab and the vendor

Warm RF coupler conditioning


Pre-conditioned in pairs at IJCLab



Travelling wave up to 400 kW
Standing wave up to 170 kW


Warm RF coupler conditioning

Pre-conditioned in pairs at IJCLab




Travelling wave up to 400 kW
Standing wave up to 170 kW

Conditioning in the CM at FREIA



(ESS CM05)




**Standing wave up to 400 kW in a
cryomodule (off resonance $\Delta f \gg BW$)**

Warm RF coupler conditioning




Pre-conditioned in pairs at IJCLab




Travelling wave up to 400 kW
Standing wave up to 170 kW

Conditioning in the CM at FREIA



Standing wave up to 400 kW in a cryomodule (off resonance $\Delta f \gg BW$)


Comparison



Warm RF coupler conditioning



Pre-conditioned in pairs at IJCLab




Travelling wave up to 400 kW
Standing wave up to 170 kW

Outcome

- Outgassing in CM is mainly below 100 kW (multipacting barrier MP)
 - Spatial distribution of RF is different from the configuration in CM
- In CMs, 24h x 3-4 days up to duty cycle 4.5% to completely clean the MP bands
- Reliability of the RF system during this time is crucial


Conditioning in the CM at FREIA



(ESS CM05)

Standing wave up to 400 kW in a cryomodule (off resonance $\Delta f \gg BW$)

Comparison





Warm RF coupler conditioning (cont'd)



CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100



Warm RF coupler conditioning (cont'd)



- Some couplers were conditioned twice without being exposed to air when broken stepper motors were replaced

CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100



Warm RF coupler conditioning (cont'd)



- Some couplers were conditioned twice without being exposed to air when broken stepper motors were replaced
- Some couplers were repaired & recycled from disqualified cavity strings due to a vacuum leak

CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100



Warm RF coupler conditioning (cont'd)



- Some couplers were conditioned twice without being exposed to air when broken stepper motors were replaced
- Some couplers were repaired & recycled from disqualified cavity strings due to a vacuum leak

CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100

→ The gate valve to the pumping station was closed



Warm RF coupler conditioning (cont'd)



- Some couplers were conditioned twice without being exposed to air when broken stepper motors were replaced
- Some couplers were repaired & recycled from disqualified cavity strings due to a vacuum leak

CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100

→ The gate valve to the pumping station was closed

→ Only one pumping station was connected



Warm RF coupler conditioning (cont'd)



- Some couplers were conditioned twice without being exposed to air when broken stepper motors were replaced
- Some couplers were repaired & recycled from disqualified cavity strings due to a vacuum leak

CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100

→ The gate valve to the pumping station was closed

→ Only one pumping station was connected

→ Only one RF station was connected

Warm RF coupler conditioning (cont'd)



- Some couplers were conditioned twice without being exposed to air when broken stepper motors were replaced
- Some couplers were repaired & recycled from disqualified cavity strings due to a vacuum leak
- There is a big variation in conditioning time: from 10 h to 100 h, even under the same conditions

CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100

→ The gate valve to the pumping station was closed

→ Only one pumping station was connected

→ Only one RF station was connected

Warm RF coupler conditioning (cont'd)



- Some couplers were conditioned twice without being exposed to air when broken stepper motors were replaced
- Some couplers were repaired & recycled from disqualified cavity strings due to a vacuum leak
- There is a big variation in conditioning time: from 10 h to 100 h, even under the same conditions
- More active pumping during assembly might reduce the necessary conditioning time

CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100

→ The gate valve to the pumping station was closed


→ Only one pumping station was connected

→ Only one RF station was connected

Warm RF coupler conditioning (cont'd)



- Some couplers were conditioned twice without being exposed to air when broken stepper motors were replaced
- Some couplers were repaired & recycled from disqualified cavity strings due to a vacuum leak
- There is a big variation in conditioning time: from 10 h to 100 h, even under the same conditions
- More active pumping during assembly might reduce the necessary conditioning time
- RGA sometimes observed CH and oxygen have a negative correlation



CM #	FPC1	FPC2	# of pumps	hours
CM02	CPL01	CPL04	1	112
CM04	CPL11	CPL03	1	67
CM02	CPL01	CPL04	2	9
CM05	CPL14	CPL18	2	66
CM03	CPL06	CPL26	1	109
CM01	CPL10	CPL12	2	90
CM04	CPL32	CPL05	2	147
CM03	CPL06	CPL26	2	12
CM06	CPL11	CPL20	2	66
CM07	CPL25	CPL30	2	48
CM08	CPL21	CPL15	2	65
CM09	CPL27	CPL28	2	30
CM10	CPL23	CPL24	2	10
CM11	CPL22	CPL19	2	26
CM12	CPL03	CPL09	2	92
CM10	CPL23	CPL24	2	9
CM09	CPL16	CPL17	2	67
CM13	CPL27	CPL28	2	100


→ The gate valve to the pumping station was closed

→ Only one pumping station was connected

→ Only one RF station was connected





Cryomodules' Cooling





- Thermal shields cooled with LN2 (24 h min)

Cryomodules' Cooling




- Thermal shields cooled with LN2 (24 h min)
- Thermalization times are very important for when cooling with LHe
 - Shorter cooling times, so
 - Less LHe spent during cooldown



Cryomodules' Cooling




- Thermal shields cooled with LN2 (24 h min)
- Thermalization times are very important for when cooling with LHe
 - Shorter cooling times, so
 - Less LHe spent during cooldown
- Cooling rates above 1 K/min





Cryomodules' Cooling




- Thermal shields cooled with LN2 (24 h min)
- Thermalization times are very important for when cooling with LHe
 - Shorter cooling times, so
 - Less LHe spent during cooldown
- Cooling rates above 1 K/min





Cryomodules' Cooling



- Thermal shields cooled with LN2 (24 h min)
- Thermalization times are very important for when cooling with LHe
 - Shorter cooling times, so
 - Less LHe spent during cooldown
- Cooling rates above 1 K/min
 - To avoid potential Q-disease but
 - Thermal contraction slow




Cryomodules' Cooling





- Thermal shields cooled with LN2 (24 h min)
- Thermalization times are very important for when cooling with LHe
 - Shorter cooling times, so
 - Less LHe spent during cooldown
- Cooling rates above 1 K/min
 - To avoid potential Q-disease but
 - Thermal contraction slow



As A. Miyazaki presented:
no flux expulsion required for these spoke cavities




Cryomodules' Cooling



- Thermal shields cooled with LN2 (24 h min)
- Thermalization times are very important for when cooling with LHe
 - Shorter cooling times, so
 - Less LHe spent during cooldown
- Cooling rates above 1 K/min
 - To avoid potential Q-disease but
 - Thermal contraction slow



As A. Miyazaki presented:
no flux expulsion required for these spoke cavities




wide spread BUT no individual difference among modules and no problem for normal operation

Cryomodules' Heat Loads and Q_0




With both cavities at 9 MV/m



Cryomodules' Heat Loads and Q_0



With both cavities at 9 MV/m




HLs measured with a volumetric flowmeter at T room and P atm

Cryomodules' Heat Loads and Q_0



With both cavities at 9 MV/m




HLs measured with a volumetric flowmeter at T room and P atm

Cryomodules' Heat Loads and Q_0



With both cavities at 9 MV/m *FE Onset*




HLs measured with a volumetric flowmeter at T room and P atm

Cryomodules' Heat Loads and Q_0



With both cavities at 9 MV/m *FE Onset*




HLs measured with a volumetric flowmeter at T room and P atm

- The static heat load
 - Influenced by Thermo Acoustic Oscillation (TAO) → valve configuration changed → impact in flow
 - Higher than dynamic → due to the system being in a different thermalization state (??)
 - Dominates the cryogenic loss
- The RF power dissipation is within error bars, compared to static heat load

Cryomodules' Heat Loads and Q_0




With both cavities at 9 MV/m *FE Onset*



HLs measured with a volumetric flowmeter at T room and P atm

Static heat load




- The static heat load
 - Influenced by Thermo Acoustic Oscillation (TAO) \rightarrow valve configuration changed \rightarrow impact in flow
 - Higher than dynamic \rightarrow due to the system being in a different thermalization state (??)
 - Dominates the cryogenic loss
- The RF power dissipation is within error bars, compared to static heat load

Cryomodules' Heat Loads and Q_0




With both cavities at 9 MV/m *FE Onset*



HLs measured with a volumetric flowmeter at T room and P atm

Static heat load




- The static heat load
 - Influenced by Thermo Acoustic Oscillation (TAO) → valve configuration changed → impact in flow
 - Higher than dynamic → due to the system being in a different thermalization state (??)
 - Dominates the cryogenic loss
- The RF power dissipation is within error bars, compared to static heat load
- Good cavity performance → RF power dissipation in pulsed operation < than the resolution of evaporation method in the CM

Cryomodules' Heat Loads and Q_0




With both cavities at 9 MV/m *FE Onset*



HLs measured with a volumetric flowmeter at T room and P atm

Static heat load




- The static heat load
 - Influenced by Thermo Acoustic Oscillation (TAO) → valve configuration changed → impact in flow
 - Higher than dynamic → due to the system being in a different thermalization state (??)
 - Dominates the cryogenic loss
- The RF power dissipation is within error bars, compared to static heat load
- Good cavity performance → RF power dissipation in pulsed operation < than the resolution of evaporation method in the CM

Thermal screens LN2 cooling → 50 K at ESS → improvement of static heat load is highly expected


No significant cavity degradation after the vertical tests



Field Emission




Field Emission



- No HPR after VT and before CM assembly → challenging objective for IJCLab
 - except 06 and 23 (not re-tested afterwards)
- Field emission (X-ray) was not clearly observed in some CMs up to the administrative limit
- No major degradation was observed

Field Emission




- No HPR after VT and before CM assembly → challenging objective for IJCLab
 - except 06 and 23 (not re-tested afterwards)
- Field emission (X-ray) was not clearly observed in some CMs up to the administrative limit
- No major degradation was observed

All cavities reached the nominal gradient 9 MV/m

IJCLab's method proved succesful


Risk of Quench and Protection



- Multipacting is a major challenge in spoke cavities
- Quench at low fields ($< 1\text{MV/m}$) is possible \rightarrow trigger “global” quench \rightarrow problem for ESS
- Need to stop RF powering in case of “local” quench
- Quench detection and interlock strategy were crucial
 - fast interlock at low field BEFORE the first powering
 - pressure interlock
 - quench detection system via on-line evaluation of decay constant with FPGA




Cold Tuning System and Lorentz-force Detuning







Cold Tuning System and Lorentz-force Detuning





- All cavities reached target frequency within specifications

Cold Tuning System and Lorentz-force Detuning





- All cavities reached target frequency within specifications
- Piezo range from -40 V to 200 V

Cold Tuning System and Lorentz-force Detuning



- All cavities reached target frequency within specifications
- Piezo range from -40 V to 200 V
- Piezo range is enough to compensate for LFD
- Note: active compensation tested only in 1st series module (LLRF not ready at the time)

Cold Tuning System and Lorentz-force Detuning



- All cavities reached target frequency within specifications
- Piezo range from -40 V to 200 V
- Piezo range is enough to compensate for LFD
- Note: active compensation tested only in 1st series module (LLRF not ready at the time)




Need to stress test prototype motor and min one of the series



Lessons Learned



- FREIA has tested series cryomodules for **2 ½ years**  competence and expertise acquired
BUT it did not come for free



Lessons Learned



- FREIA has tested series cryomodules for **2 ½ years** → competence and expertise acquired

BUT it did not come for free

- Main Points
 - He recovery capacity: increased mid testing (not a bottleneck)
 - Heat load measurement: add new flowmeter with a lower range in parallel
 - FPC cooling: add ScHe circuit
 - RF stations
 - Failures with tetrodes, power supplies and amplifiers → problems with schedule
 - Careful optimisation of operation parameters, risk analysis and availability of spare parts



Lessons Learned



- FREIA has tested series cryomodules for **2 ½ years** → competence and expertise acquired

BUT it did not come for free

- Main Points

- He recovery capacity: increased mid testing (not a bottleneck)
- Heat load measurement: add new flowmeter with a lower range in parallel
- FPC cooling: add ScHe circuit
- RF stations
 - Failures with tetrodes, power supplies and amplifiers → problems with schedule
 - Careful optimisation of operation parameters, risk analysis and availability of spare parts

→ **Necessary**

Lessons Learned



- FREIA has tested series cryomodules for **2 ½ years** → competence and expertise acquired

BUT it did not come for free

- Main Points

- He recovery capacity: increased mid testing (not a bottleneck)
- Heat load measurement: add new flowmeter with a lower range in parallel
- FPC cooling: add ScHe circuit
- RF stations
 - Failures with tetrodes, power supplies and amplifiers → problems with schedule
 - Careful optimisation of operation parameters, risk analysis and availability of spare parts
- In day-to-day activities
 - Good planning and overview, and
 - Good understanding of what processes or activities can be done or prepared in parallel

→ **Necessary**

Lessons Learned



- FREIA has tested series cryomodules for **2 ½ years** → competence and expertise acquired

BUT it did not come for free

- Main Points

- He recovery capacity: increased mid testing (not a bottleneck)
- Heat load measurement: add new flowmeter with a lower range in parallel
- FPC cooling: add ScHe circuit
- RF stations
 - Failures with tetrodes, power supplies and amplifiers → problems with schedule
 - Careful optimisation of operation parameters, risk analysis and availability of spare parts
- In day-to-day activities
 - Good planning and overview, and
 - Good understanding of what processes or activities can be done or prepared in parallel

→ **Necessary**

→ **Essential**



Future Prospects



- Testing of a canted-cosine Theta (CCT) superconducting magnet → Fall 2023



Future Prospects



- Testing of a canted-cosine Theta (CCT) superconducting magnet → Fall 2023
- Testing of a low temperature superconducting magnet for the iFAST Project → 2024





Future Prospects



- Testing of a canted-cosine Theta (CCT) superconducting magnet → Fall 2023
- Testing of a low temperature superconducting magnet for the iFAST Project → 2024
- Testing of a superconducting magnet for Hitri+ → 2025





Future Prospects



- Testing of a canted-cosine Theta (CCT) superconducting magnet → Fall 2023
- Testing of a low temperature superconducting magnet for the iFAST Project → 2024
- Testing of a superconducting magnet for Hitri+ → 2025
- FREIA is under discussion with SCK-CEN to work on the MYRRHA project testing
 - Single spoke cavities (x60)
 - Single spoke cavity cryomodules (x30)





Future Prospects



- Testing of a canted-cosine Theta (CCT) superconducting magnet → Fall 2023
- Testing of a low temperature superconducting magnet for the iFAST Project → 2024
- Testing of a superconducting magnet for Hitri+ → 2025
- FREIA is under discussion with SCK-CEN to work on the MYRRHA project testing
 - Single spoke cavities (x60)
 - Single spoke cavity cryomodules (x30)



Logistics will be very important

Future Prospects



- Testing of a canted-cosine Theta (CCT) superconducting magnet → Fall 2023
- Testing of a low temperature superconducting magnet for the iFAST Project → 2024
- Testing of a superconducting magnet for Hitri+ → 2025
- FREIA is under discussion with SCK-CEN to work on the MYRRHA project testing
 - Single spoke cavities (x60)
 - Single spoke cavity cryomodules (x30)



Logistics will be very important

FREIA has the expertise for series testing



Thank you for listening

And also thanks to:

- FREIA team for all the hard work
- IJClab' and ESS' colleagues for fruitful discussions
- The SRF23 organizers for the opportunity to give this talk