

# Twenty years of cryogenic operation of the FLASH superconducting linac

21st International Conference on Radio-Frequency Superconductivity

Serena Barbanotti  
Grand Rapids, 27<sup>th</sup> June 2023

HELMHOLTZ



# Summary

## Twenty years of cryogenic operation of the FLASH superconducting linac

### 01 The FLASH SC linac and its cryo distribution

- The FLASH facility
- Cryogenic supply
- The FLASH cryomodules

### 02 The FLASH cryoplant

- Layout
- Main parameters

### 03 Evolution of the cold linac

- From TTF to FLASH
- Main shutdowns

### 04 The 2022 shutdown

- Motivation and challenges
- Preliminary tests

### 05 Operation overview


- New operation scheme
- Heat loads
- Pressure stability
- Downtime

### 06 Conclusions

# The FLASH SC linac and its cryogenic distribution

# The FLASH facility


Status in 2023



# FLASH cryogenic supply

In 2023


- One 3.9 GHz and seven 1.3 GHz **SC cryomodules**
- Cooled by one **former HERA cryoplant**, shared with **CMTB** (2006), **AMTF** (2010), **ALPS II** (2021)



# FLASH cryogenic supply

In 2023


- Two parallel **warm compressors** for 2 K operation, shared with CMTB and the SCU test field (starting 2023)
- **Redundant** cryoplant and compressors available (not used in the last 15 years)



# FLASH cryogenic at the linac


2023

- Helium (40-80K, 5-8K) from cryoplant distributed to two branches at the Fermi-box
- 4K helium pre-cooled in the 2K heat exchanger at the Fermi-box
- Three **Joule-Thompson valves** distribute liquid helium to the three linac sections





# The FLASH cryomodules

In 2023



Position	Module S/N	Module type	First installation	Coupler type
ACC39	-	3.9 GHz	2009	3.9 GHz
ACC1	3***	TTF type II	2009	TTF III
ACC2	PXM2.1	XFEL prototype	2022	TTF III
ACC3	PXM3.1	XFEL prototype	2022	E-XFEL
ACC4	4	TTF type III	2003	TTF II
ACC5	5	TTF type III	2003	TTF III
ACC6	6	TTF type III	2007	TTF III
ACC7	PXFEL1	XFEL prototype	2009	TTF III






# FLASH cryomodule operation

## Summary of cavity performances




- Upgraded waveguides allow adaptation to cavity performances (optimization ongoing)
- Performance in average 84% of the expectation from vertical tests
- No gradient degradation during operation at FLASH



# The FLASH cryoplant

# FLASH cryoplant

## Some impressions



# FLASH cryoplant


## Main parameters

- The FLASH cryogenic plant, some numbers:
  - compressor power: 1.5 MW low pressure compressors, 1.7 MW high pressure compressors
  - Maximum flow: 1000 g/s at 18 bar
  - Cooling power:

20 kW	at 40/80 K
6.8 kW	at 4.4 K
20 g/s	liquefying power
- Cryo capacity distributed among users
  - Parallel operation of FLASH, AMTF, CMTB, ALPSII demonstrated in 2023
    - Possible limitations during cool down and warm up of single test stands


# The FLASH cryoplant 1998 - 2023

DESY cryoplant 1998 - 2009



# The FLASH cryoplant 1998 - 2023


FLASH cryoplant since 2010



# Evolution of the FLASH cold linac



# From TTF (TESLA Test Facility) to FLASH

1996



## The TESLA collaboration


- Common effort of almost all laboratories using SC cavities (53 partners from 12 countries) to:
  - Increase cavity gradient from 5 to 25 MV/m
  - Reduce costs



DESY. | Twenty years of cryogenic operation of the FLASH SC linac | Serena Barbanotti, 27/06/2023

## TESLA Test Facility

- First beam tests with gun only in 1996
- First cryomodule installed 1996 with one cavity
- First test with CC and beam in 1997







# From TTF to FLASH

1997-2002

- First TTF type cryomodules (each with eight cavities) at position ACC1 / ACC2
- First bunch compressor, first undulator
  - February 2000: first lasing with a SASE FEL at a VUV wavelength of 109 nm worldwide
- In 2002: test of the Super-Structure module at ACC1, first blade tuner




Super-Structure: 2x7-cell structures

# From TTF to FLASH

2003-2005

- Refurbished (M3\*) and new cryomodules M4, M5 (TTF type III modules, basis for XFEL, LCLSII, Shine, ...)
- Second bunch compressor with transfer line BCBTL2
- New injector area (ACC1 moved, Module Super-Structure, ½ BCBTL1, VBs ACC1 and CC removed)

→ FLASH becomes an FEL user facility (SASE 13 nm in 4/2006)



# FLASH


## 2007 and 2009 shutdowns

### 2007 shutdown

- Repair ACC5, replace ACC3, install ACC6
- 5 Hz, 1 to 800 bunches, 1 MHz, 500 kHz, ...  
SASE: 6.5 nm

### 2009 shutdown


- Replace ACC1, install ACC39 and ACC7
- 10 Hz, 1 to 800 bunches, 1 MHz, 500 kHz, ...  
SASE: 47 – 4.1 nm



# FLASH

## 2022 shutdown


- Energy upgrade: PXM2.1 and PXM3.1 installed at ACC2-3 ( 1250  $\rightarrow$  1350 MeV )



# The 2022 shutdown

# FLASH2020+

Towards an extraordinary XUV- and soft X-ray facility



**Phase 0**  
 Energy upgrade  
 3<sup>rd</sup> BC (FLASH2)  
 TDS (FLASH2)  
 Injector Laser  
 Afterburner FLASH2

**Phase 1**  
 Variable gap undulators (FLASH1)  
 Pump-probe laser (FLASH1)  
 Laser heater in 1st BC  
 New 2nd bunch compressor (BC)

**Phase 1+**  
 High rep.rate seeding (FLASH1)  
 Photon diagnostics (FLASH1)

**Phase 2**  
 New variable gap undulators +  
 chicanes  
 for new lasing concepts (FLASH2)

- More details: see talk **TUIAA02**, M. Vogt: “FLASH 2020+ Upgrade Project”

# Motivation and challenges

## For the SC linac

- **Scope of the shutdown** for the SC linac: **energy upgrade 1250 → 1350 MeV**
  - replace ACC2-ACC3 with 2 XFEL prototype cryomodules
    - new cryogenic connections ACC2-FC and ACC3-EC
    - new and modified valves
- **Challenge:** incomplete documentation of older components would fail regulatory requirements → **operating pressure reduced to <0.5 bar** for all pressurized components in the linac
  - test performed at FLASH before final OK
  - bigger (or more) relief valves needed, with pneumatic loading system to be independent from back pressure and have a higher reclosing pressure
    - new venting test of a XFEL cryomodule


See poster  
MOPMB082



# 0.5 bar (375 Torr) operation preliminary tests

## To verify feasibility

- Two tests performed:
  - Operation at 0.5 bar for 3 days with AMTF operation in parallel (incl. WU/CD)
  - Warm up and cool down test with the 0.5 bar limit → new 5K valve to speed up cool down
- Conclusions:
  - Operation within the new pressure possible
  - Temperature increase at the 40/80 K thermal shield and couplers observed, but temperature stabilised at higher T
  - Impact of RF, beam and magnet operation not critical
  - Impact of dynamic operations in AMTF / CMTB in parallel not critical






# Venting test

## XM-3 at CMTB





- Cryomodule in cold and stable state, all supply valves closed → open isolation vacuum pump port at the cryomodule
- From pressure rise in the piping we calculate the heat flux to the single circuit (parameter needed to size the relief components)
- Further consequence: size of pump ports reduced from DN100 to DN80



*(Further details to be published soon)*

# Overview of the cryogenic activities

## Some impressions




# Operation overview

# Cooling cycles and cool down with new configuration

## One valve added after CD test

- Since 2002, FLASH has seen 9 cool-downs and 8 warm-ups
- Average cool-down/warm-up time (to 4 K): ~10 days each
- Expected a slightly longer cool down with 0.5 bar operation, but no substantial difference in cool down duration observed
  - Some issues with mixing warm gas and cold gas in the 4 K forward line → more practice needed!
  - FEL sub-cooler box in 2017 already cold, in 2022 cooldown together with FLASH



# One year of 0.5 bar operation

## First “impressions”

- The system is more sensitive to disturbances
  - A faster reaction time is needed
- It is easier to loose precious (!) helium in case of outages (relief valves open at 0.5 bar)
- Recovery after an outage takes longer, more caution needed to avoid opening relief valves
- The system is more sensitive to changes in parallel systems (AMTF / ALPS II / CMTB)
  - More caution needed during parallel operation and transient operations

# Static heat loads

## 2K and 40/80K static heat loads

- Calculated during operation as flow  $\times$  delta enthalpy
  - Enthalpy for the 2K evaporated helium: constant temp 2K, and pressure 31 mbar (23 Torr)
- Average 2K static heat load 30 W, 40/80 K static heat load  $\sim$ 1 kW
- No reliable data for the 5/8 K circuit (liquid in the pipes, no known quality)



40/80 K static heat loads				
<i>Time</i>	<i>RF energy (GeV)</i>	<i>P (bar)</i>	<i>Flow (g/s)</i>	<i>Heat load (W)</i>
12/2018	0	11.8	15.4	796
12/2019	0	12.3	24.8	799
12/2020	0	12.8	16.8	888
12/2022	0	1.4	4.9	889
04/2023	0	1.4	8.9	1111

2 K static heat loads			
<i>Time</i>	<i>RF energy (GeV)</i>	<i>P (bar)</i>	<i>Heat load (W)</i>
12/2018	0	1.6	23
12/2019	0	1.6	35
12/2020	0	1.6	26
12/2022	0	1.4	28
04/2023	0	1.4	33

# Pressure stability

## Now and then


- Average pressure stability better than 0.1 mbar (75 mTorr)
- Values not affected by 0.5 bar operation



# Cryoplant availability

Since 2000

- Average availability during operation 99%
  - includes HERA till 04.2007
  - Longer shutdowns not included
- Does not correspond to cryo-downtime of FLASH
  - does not include machine set-up time
- Typical sources of downtime:
  - Power supply
  - Cooling water
  - Compressors





# Conclusions

# Conclusions

## From TTF to FLASH2020+

### FLASH linac

- FLASH is an FEL user facility since 2005
- The FLASH linac is in continuous development
- The linac has been a test bench for many accelerator components that are now considered “standard” and is the basis for XFEL modules (and LCLS II, Shine, ...):
  - TTF-like cavities and couplers
  - Tuning systems
  - HOM couplers, BPMs, magnetic shielding, ...

### Outlook

- Major shutdown of the warm section starts in summer 2024
  - The cold linac will be warmed up, no work on the cold linac expected



# Thanks

to all the colleagues who helped for this presentation

AND

to all the colleagues who made FLASH possible (the list is too long for this page)

**And thank you  
for your attention!**

## Contact

Deutsches Elektronen-  
Synchrotron DESY

[www.desy.de](http://www.desy.de)

Serena Barbanotti  
MKS Group  
[serena.barbanotti@desy.de](mailto:serena.barbanotti@desy.de)  
+49 (0)40 8998-0